

TEST REPORT

DATE: 05-24-2024

Page 1 of 1

TEST NUMBER: 0307959

CLIENT	Go Green
---------------	----------

TEST METHOD CONDUCTED	ASTM F1551 Water Permeability of Synthetic Turf Systems and Permeable Bases, DIN 18-035
------------------------------	---

DESCRIPTION OF TEST SAMPLE	
IDENTIFICATION	Petmaxx 90
ROLL NUMBER	G36711B
CONSTRUCTION	Turf
REFERENCE	PO #17807


GENERAL PRINCIPLE

The test procedure is used to determine the flow rate of rainfall through a material. A volume of water is poured through the surface and timed. Calculations are then made on the inches of water that would pass through the substrate per hour. The sample was tested as received.

TEST RESULTS

SAMPLE IDENTIFICATION	RESULTS
Petmaxx 90	1441.3 Inches/Hour
	4.30 Sec/6" zone
	469.8 Gal/min/yd ²

APPROVED BY:



This report is provided for the exclusive use of the client to whom it is addressed. It may be used in its entirety to gain product acceptance from duly constituted authorities. This report applies only to those samples tested and is not necessarily indicative of apparently identical or similar products. This report, or the name of Professional Testing Laboratory, LLC, shall not be used under any circumstance in advertising to the general public.